

Items.	Per.	Quantity.	Cost.
Rough stone work, old	C. Yd.	750	
Do new	do	4,236	
Apron	do	1,206	
Earthwork to bund	do	16,976	
Do breach	do	19,999	
Clearing kodi channel hard soil	do	19,438	
Excavating foundation do	do	1,190	
Turfing bund	S. Yd	7-26	
Grade stones	Each.	19	
Bench mark	Each.	2	
Gauge stone	No.	1	
Repairing Sluice No. I	R. Ft.	60	
Gibbet stones	L. Sum.		
Clearing jungle	L. Sum.		
Hutting allowance	do		
Brick in surki mortar	C. Ft.	3,078	
Plastering	S. Yd.	17-70	
Slab stones over kodi wall	S. Ft.	374	
Do stones	No.	19	
Pin stones	No.	18	

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring Danavadi Dyamanakere, Shimoga Taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

A. S. NAGAVKAR,
Executive Engineer.

MYSORE SPECIAL IMPROVEMENTS DIVISION.

ADVERTISEMENT.

The 8th January 1889.

Notice is hereby given that sealed tenders will be received at the office of the Sanitary Engineer, Special Improvements Division, up to 20th January 1889, for reconstructing the Eastern Frontage of the Market at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st March 1890.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's office at Mysore between the hours of 12 to 5 p. m.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes as earnest money, and be superscribed "Tender for reconstructing the Eastern Frontage of Market at Mysore;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract.

Quantity.	Items of Work.	Per.	Rate.
1,079	Earthwork excavation and filling the same in the basement ..	C. Yd.	
9,209	Concrete below foundation ..	C. Ft.	
14,193	Foundation with brick in chunam ..	do	
5,051	Basement with brick in chunam ..	do	
16,849	Superstructure, Lower story, with brick in chunam ..	do	
3,730	Superstructure, Upper story, brick in chunam ..	do	
6,079	Archwork with brick in chunam ..	do	
926	Cornice work ..	R. Ft.	
720	Thin cornice work to parapet ..	do	
70	Moulding work of windows, &c., ..	do	
8	Mantapam stone posts (cut) to Balcony each 1' x 1' x 7' including cutting base and top, &c, complete ..	Each.	
8	Brackets stones to Balcony at 1' x 1' x 4' including. do ..	do	
1,555	Burnt stone slabs to steps ..	S. Ft.	
45.54	Tie rods of roof 1 " Dr. ..	Cwt.	
39.30	Fish plates, flat bar iron 4 " x 1/2 " ..	do	
623.42	Plastering Lower story ..	Sqr.	
65.17	Do Upper story ..	do	
688.59	Whitewashing ..	do	
88.53	Flooring with slabs ..	do	
12.301	Segmental arched roof 1/2' thick including one course of flat tiles and concrete over roof..	C. Ft.	
2	Sets of centrings to arched roof ..	L. S.	
23.02	Terracing ..	Sqr.	
	Door, s batten, including frames, bolts, hinges, &c., complete (No. 4. 4' x 7') (No. 4. 3' x 7') ..	Each.	
4	Battened windows to Lower story 3' x 5' including iron bars, &c., complete ..	do	
10	Do do 3' x 6' do without iron bars ..	do	
2,361 1/2	Planked supper boards to semicircular archways of verandahs, including frames, &c., complete ..	Sq. Ft.	
603 1/2	Teakwood work wrought and put up complete ..	C. Ft.	
110.00	Wood-oiling to wood work ..	Sqr.	
2	Ornamental work above balcony to parapets and gables ..	Each.	
1	Ornamental work of parapets on the sides of Upper story ..	L. S.	
4	Finials above pedestals of Upper story ..	Each.	
4	Ornamental brackets over parapets of Lower story ..	do	
2	Ornamental key stones to main passage..	do	
8	Ornamental columns at front and rear of Upper story ..	do	

STANDISH LEE,
Sanitary Engineer.

Visitors to the Mysore Government Museum, Bangalore, during the month of December 1888, were 17,747 in number, averaging, exclusive of Sundays 683 daily.

SIGNATURES MADE IN—										Total of Signatures.		Unable to sign but tally kept.	Total of Visitors.	Unable to sign No. of—		Total of Visitors.
English.	European.	Native.	Tamil.	Teluga.	Kanarese.	Hindustani.	Mahratta.	Guzarati.	Malayalam.	Marvadi.	Males.			Females.	Men and Boys.	
603	1,554	801	193	1,322	380	40	3	6	6	4,700	208	12,839	17,747	6,943	5,896	17,747

J. CAMERON.